

Curbs Plus, Inc.

1200 Carline Road
 Rossville, GA. 30741
 PH (706) 858-1188 / FAX (706) 866-2339

APPROVED BY: _____

DATE APPROVED: _____

CPSR-1 (Square to Round) Transition Cover

STANDARD FEATURES

1. 18 Ga. Galvanized Steel Construction.
2. Fully Welded Watertight One-piece Construction.
3. Welds Coated after Fabrication.
4. 1" Thick Neoprene Faced Fiberglass Insulation.
5. Cross Broken for Positive Water Run-Off.
6. Available on all Roof

OPTIONS:


- 1.
- 2.
- 3.
- 4.

PROJECT NAME: _____


CITY, STATE: _____

CUSTOMER: _____

JOB NUMBER: _____




PLAN VIEW



ELEVATION

Notes:

- * (1) **Inside Cap Dimension = Curb O.D. plus 1-1/2"** on all "Insulated" Conventional Roof Curbs (CPC-1, 2, 3) and, **1/2"** on all Metal Building Roof Curbs, and "Non-Insulated" Conventional Roof Curbs (CPC-4, 5).
- ** (2) **Inside Diameter = Pipe O.D. plus 1/2"**.
- (3) **Available on all Roof Curb Styles.**
- (4) **See Conventional or Metal Bldg. Sections for Curb Selection.**
- (5) **Attach this sheet to Selected Roof Curb Drawing.**



SECTION A-A

QUANTITY	INSIDE CAP DIM. *	OUTSIDE CURB DIM.	"D" (Inside Dia.) **	"H"	TAG
	X	X			
	X	X			
	X	X			
	X	X			
	X	X			